



Nassau County Sheriff's Office

Sheriff Bill Leeper

September 28, 2020

Notice of Addendum to: RFP; NCSO-20-R-002: NASSAU COUNTY SHERIFF'S OFFICE PUBLIC SAFETY TRAINING COMPLEX

ADDENDUM NCSO-20-R-002-1

Notice is hereby given regarding the Nassau County Sheriff's Office ("NCSO") solicitation for **Request for Proposal ("RFP") for Land Clearing & Earth Work – Nassau County Sheriff's Office Public Safety Training Complex** **due date has been changed**. Interested and qualified respondents may submit a Proposal, according to the requirements previously advertised, to the Nassau County Sheriff's Administrative Services Management and Purchasing Policy. All proposal are due by or before 4:00PM (EST) on **October 16th, 2020**. Any proposal delivered to or received after the 4:00PM deadline will not be considered and shall be returned unopened to the addressee.



Nassau County Sheriff's Office

Sheriff Bill Leeper

September 28, 2020

Notice of Addendum to: RFP; NCSO-20-R-002: NASSAU COUNTY SHERIFF'S OFFICE PUBLIC SAFETY TRAINING COMPLEX

ADDENDUM NCSO-20-R-002-2

Notice is hereby given regarding the Nassau County Sheriff's Office ("NCSO") solicitation for **Request for Proposal ("RFP") for Land Clearing & Earth Work- Nassau County Sheriff's Office Public Safety Training Complex.** The following revision is being made to the original **Request for Proposal.**

Revision to Section:

PART III: GENERAL REQUIREMENTS

B. Scope of Work:

(Additional language to Scope of Work)

The US and Canadian guidance for interior slopes of gun ranges is that the slopes should be no flatter than 30 degrees (1.7 horizontal:1.0 vertical). The General Notes (see Attachment) on drawing IN-1, note # 36, states the "...fill shall be placed in eight (8) inch lifts and compacted to ninety-five percent (95%) within plus or minus of two percent (2%) of the Optimum Moisture Content using the Standard Procter Density Test (ASTM 698)..." **This provision of the General "Notes" is hereby waived by NCSO regarding the moisture content during earthwork compaction but will still require the fill to be compacted to 95 percent of the ASTM D-698 maximum density.**

Administrative Office• 77151 Citizens Circle, Yulee, FL 32097• (904) 225-0331 or 225-0332

Callahan/Hilliard/Bryceville Toll Free: (855) 725-2630

Detention Center• 76212 Nicholas Cutinha Road, Yulee, FL 32097• (904) 225-9185 or

Toll Free: (855) 725-2631 • **Jail Administration Fax:** (904) 548-4015

Communications/After Hours • (904) 225-5174• or Toll Free: (855) 725-2632